

| Item 10 - Assets, Community and Environment | | | | | | | | | | |
|--|----------------|--------------|--|---|-----------|--|--|----------|-----|---|
| Churchyard and Cemetery - Lychgates Preservation - Summary of Quotations July 2019 | | | | | | | | | | |
| Contractor | Contact | Telephone | Email | Address | Visit Fee | Work to be carried out | Work not included | Total | VAT | Comments |
| Bensleys | Brian Browne | 01273 600700 | admin@bensleys.co.uk | 10 De Montford Road Brighton BN2 3AU | 100.00 | | | | | Advised by letter cannot offer much assistance? |
| Floyd Consult | Tim Floyd | 01562 885800 | tim@floydconsult.co.uk | 68 Mill Lane Solihull B93 8NW | 1,220.00 | Assessing current levels of wood borer beetle activity will be difficult outside of the flight season (the only way to confirm activity is to find emerging adults in the flight season – roughly March – July). However an assessment of magnitude and extent of fungal decay and wood borer damage could be achieved. In this case a microdrill (which I use) would be very useful. A report would be issued including observations and recommendations which would detail extent of damage and appropriate forms of remediation. It would seem the entire Lychgate structure requires assessment. | | | | add Site visit fee includes travel and report |
| Gould and Company | Godfrey Baker | 01444 452600 | gb@gouldco.co.uk | 2 Lucastes Mews Paddockhall Road RH16 1HE | | | | | | Unable to visit site until later in year due to workload |
| Insitu SCP | Gary Moakes | 01403 740050 | info@insituscpc.co.uk | Palmerston House Farren Court The Street Cowfold RH13 8BP | N/A | Stage 1 We will carry out a programme of de-frassing the worst affected areas by removing the loose and friable material in order to get back to sound timber prior to applying treatment. We will then brush down all timbers to remove surface dust and debris. We will then pressure spray two applications of a dual purpose insecticide/fungicide fluid treatment to the exposed timbers in both gates. This will ensure maximum saturation of the timbers. In addition to the treatments detailed above we would also brush apply a deep penetrating insecticidal paste into large dimension and heavily infested timbers and where possible inject insecticidal fluid through old flight holes. Fluids must be applied at a heavy dosage. Death Watch Beetle extermination can be exceptionally difficult to achieve – additional treatments MAY be required. NB We are unable to offer a guarantee for this work due to the nature and location of the timbers. | | 1,920.00 | Add | Site visit 17/7, report/quote received Stage 2 and 3 in report/not quoted |
| MacConvills | Toby Rolleston | 01273 692610 | mail@macconvilles.com | Heversham House 18-22 Boundary Road Hove BN3 4EF | N/A | | | | | Site visit 31/8 Proposal awaited |
| Preservation Treatments | David Morton | 01276 664660 | info@preservationtreatments.co.uk | Belmont House Belmont Road Camberley GU15 2NZ | N/A | RESIN REPAIRS: Our Operatives will carry out the following work to the areas indicated on the attached plans no. 95501 and 95501.1: • Lay protective sheeting down around the area where we are working. • Rake out all old decayed and loose timbers from the base and the vertical cracks to the front left and rear left vertical supports on the North Lychgate. • Cut away the loose, decayed timber from the base of the rear right hand corner support on the North Lychgate. • Cut away decayed timber from the end of the sole-plate at the front right-hand side of the West Lychgate. • Cut away and rake out the decayed timber from the underside of the sole-plate at the rear left-hand end of the West Lychgate. • Form a shutter around the bottom of the front left and rear left-hand vertical supports on the North Lychgate and pour Rotafix TG6 structural resin. The shutters will need to stay in-situ for at least 24 hours. • In all other areas, we will fill the voids with Rotafix Moulding Mortar to the existing lines. • Clear site and leave tidy. Note: We have allowed to use up to 14 litres of | Subsequent "graining" of the surface and any surface decoration, oiling of timbers will be carried out by your maintenance contractor, under separate contract and cost. ATTENDANCE WORK: (NOT included in our quotation) Generally provide access to all timbers to be treated. Whilst we are working in these areas, you must arrange for them to be cordoned off. You must ensure clear and safe working access for our Operatives throughout the course of this contract. | 2,709.00 | | Report dtd 15/10/18 on file |