

Appendix 3 - Contractor 3

CUCKFIELD PARISH COUNCIL


Queen's Hall, High Street, Cuckfield, RH17 5EL



3.0 PRICING

Item	Details	Qty/m2	Price/m2	Total Price
A	North of Church	26m		
B	South of Church	51m		
C	East of Church	48m		
	Total:	125m		
	A, B and C: Lay approximately 1200mm wide brick clay pavers and sand bedding as described laid across the path on existing tarmac paving including excavating at edges to achieve width and afterwards backfill with soil and grass seed.	125m	139.57	17446.25
D	West Lychgate			
D.1	Break out and excavate existing tarmac paving and bed under for approximately 200mm and remove from site.	41m2	16.74	686.34
D.2	Lay clay pavers on sand bed as described between two areas of stone paving laid across the path.	41m2	116.31	4768.71
E	Outside West Church Door			
E.1	Break out and excavate existing tarmac to existing stone paving and bed under for approximately 200mm and remove from site.	125m2	16.74	2092.50
E.2	Lay clay pavers and sand bed as described to falls and cross falls and to abut adjacent paver levels, laid to herringbone pattern.	125m2	116.31	14538.75
F	Extra over for cutting around buttresses and projections around entrance door.	17m		Included
G	Extra over any paving for working around gullies and raising and jointing to new levels in centre of paving.	1 no.		u
H	Ditto to edge of paving	3 no.		u
	Total:		139.57	39532.55

Please refer to the attached plan



CUCKFIELD PARISH COUNCIL

Queen's Hall, High Street, Cuckfield, RH17 5EL



4.0 SUMMARY

Total of Item 3.0:

£ 39,532.55

VAT (if applicable):

20%

7,906.51

Total carried to Tender:

£ 47,439.06

We, the undersigned contractor, tender to carry out the above works for the sum of
£ 47,439.06 in a timescale to be agreed.

Signed:

[Redacted Signature]

Name of Contractor:

[Redacted Name]

Address:

[Redacted Address]

Contact Name:

[Redacted Contact Name]

Email Address:

[Redacted Email Address]

Telephone:

[Redacted Telephone]

Date:

[Redacted Date]

The above tender will be open for acceptance for sixty (60) days from date of signature.