

3.0 PRICING

Item	Details	Qty/m ²	Price/m ²	Total Price
3.1	Break out existing tarmac paving for a depth of approximately 200mm for a width of 1200mm including vegetation from sides and remove from site and prepare to receive concrete paving.	570m (684m ²)	18.04 m.	10282.80
3.2	Insitu concrete paving 1200mm wide as specified 100mm thick on 100mm bed of 100mm gravel, laid in 5-metre-long panels with expansion joints, with 100mm trowelled margin to both sides and rough tamped surface generally including temporary formwork as required and backfill with topsoil at sides.	570m (684m ²)	55.86 m.	31840.20
3.3	Break out existing tarmac paving for a depth of approximately 200mm for a width of 1200mm including vegetation from sides and remove from site and prepare to receive new tarmac paving.	225m (270m ²)	22.01 m.	4952.25
3.4	* Lay two coats tarmac as specified to form paths 1200mm wide and backfill with topsoil at sides.	225m (270m ²)	78.42 m	17644.50
3.5	Extra over excavation and tarmac paving for new tarmac paving 2m wide (adjacent Gate 4).	30m	36.67	1100.10
3.6	Extra over any above paving for cell web membrane and filling with type 3 stones to areas of tree roots (provisionally).	50m ²	25.0	1250.00
3.7	Extra over any above paving for working around and maintaining existing gullies, manholes and valve pits and finishing off level.	11 No's	30.0	330.00
3.8	Break out existing tarmac under existing gates 4, 5 and 6 to create a step or ramp to allow free movement of gate and ease of access.	item		225.00
Total of 3:				69649.75

* Item 3.4 Includes for 130mm depth of sub-base & treated timber edgings to both sides of path.

4.00 GATES on perimeter of cemetery

Item	Details	Qty/m2	Price/m2	Total Price
4.1	Gate 1. Timber, double gate. Oil hinges only.	Item		Included
4.2	Gate 2. Timber, single gate. Cut back vegetation to free movement and latch, oil hinges.	Item		Included
4.3	Gate 3. Timber, single gate. As gate No.2.	Item		Included
4.4	Gate 4. Metal kissing gate and vehicular access gate combined. Cut back vegetation to free movement, oil hinges, rub down and prepare all metal surfaces for one full coat of "Hammerite" or similar.	Item		250.00
4.5	Gate 5. Metal kissing gate. Cut back vegetation to free movement, replace broken hinge, oil hinges, rub down and prepare all metal surfaces for one full coat of "Hammerite" or similar.	Item		350.00
4.6	Gate 6. Timber, single gate. Replace one post and supply and fix galvanised latch to match others on site. Oil hinges.	Item		120.00
4.7	Gate 7. Timber, single gate with spring closer. Oil hinges and supply and fix galvanised latch to match others on site.	Item		110.00
Total of 4:				830.00

5.0 SUMMARY

Total of 3.0 £ 69649.75

Total of 4.0 £ 830.00

VAT if applicable £ 14095.95

Total carried to tender £ 84575.70

We, the undersigned contractor, tender to carry out the above works for the sum of

£ 84575.70 in a timescale to be agreed.

Signed: _____

F. Atkins FRANK ATKINS

Contractor: _____

HEBART PAVING LTD

Address: _____

WELLINGTON HOUSE, HOLT BUSH POTTERIES
CRAWLEY ROAD FATGATE RH12 4SE

Email: _____

frank@hebartpaving.co.uk

Telephone: _____

01293 251155

Date: _____

12/9/19.

The above tender will be open for acceptance for 30 days from the date of signature