


Quotation		 <b>07-Mar-24</b>			
<b>Cuckfield Parish Council</b> <b>Operation Watershed</b>					
Ref.	Description -	Quantity	Unit	Rate	Total
	Preliminaries, Mobilisation, Insurances, Pedestrian and Traffic Management - Chapter 8 signage and 2-way traffic lights as required. To be read in conjunction with the Cuckfield Scope Plan.	1	item	incl.	incl.
<b>1</b>	<b><u>Courtmead Road Drainage Improvements</u></b>				
	Install new pipeline - 225mm Upvc twinwall pipe with ST1 concrete bed and surround including tarmac reinstatement to HAUC specification	65	lin m	incl.	incl.
	Install new pipeline - 225mm Upvc twinwall pipe with ST1 concrete bed and surround including reinstatement with topsoil and grass seed	90	lin m	incl.	incl.
	Excavate for and install new 1050mm diameter catchpit manhole in carriageway. Catchpit to have minimum 450mm sump below outgoing inverts.	2	nr	incl.	incl.
	<b>For the sum of (excluding VAT)</b>				<b>£55,332.60</b>
	<i>Notes:</i>				
	<i>No allowance made for highway licences.</i>				